

## Custom Built Spray Rigs - Cold Process Asphalt

*Built with the needs of today's professional roofing contractor in mind, our custom built trailer packages are the ultimate in job site efficiency, reliability, and operator safety. Superior engineering and quality construction are evident at a glance with these high production turn key spray systems designed for year around peak performance.*



### ***Popular features for your rig.***

- > 450 gal., 600 gal., or 1000 gal. permanent mount reservoir with positive floor slope.
- > 200,000 BTU mastic warmer with recirculating system for pre-warming reservoir.
- > Bulk tank mixer keeps product fresh at all times.
- > Power out & rewind hydraulic reel holds up to 500 ft. of 3/4" hose.
- > Stacking brackets allow 375 gal. tote placement on top of reservoir for gravity feed.
- > Wet and dry storage cabinets for component organization and soaking pole guns.
- > 50 gal. solvent flush tank for proper maintenance during cool weather applications.
- > High volume transfer pump for quick reservoir loading.

***Call 800-249-1349 to start planning your custom rig today!***